

LEBANESE SUSTAINABLE ENERGY

البنانية للطاقة البديلة

CONVENTIONAL
PROFESSIONAL

NO OFF01/24

Lebanese Sustainable Energy - Riad Soloh street / Bustan Bld / Tripoli - Lebanon / Tel 70-001747 / 06-205492

Quotation

STANDARD0

Project 108A Peak Load / Average 80% : 28A x 3 / 29280W OFF-GRID COMPLETE SYSTEM
System Indoor or Outdoor installation **Estimated Battery Lifetime 48months on average**

Model 3.OFFG108S0 - Standard0 Size **Line : THREE-PHASE** **PRICING 1/1/2024**
BATT.TYPE Tall Tubular Lead Acid Battery (Flooded) **ALLDAY TIME FRAME** **VALID**
RANGE LOC Lebanon - up to 200m above the sea **OFFGRID-HYBRID HIGH FREQUENCY INVERTER SOLAR SYSTEM**
G.NOTES
* Transportation & Handling Fees covers North coast areas down to Damour zone and/or (Up to 200M above sea level)
* Battery rack & inverter mount are optional for all Hybrid High/Low Frequency applications.
* Cabling pricing are not included. Cabling final pricing are based to distance needed

I.Code	Technical Description	QTY	Unit/ Price \$	Total USD
AU-1P12K1G	AUSTA/ DEYE 3phase Premium Hybrid inverter -Output: 12000w / PV160-800v/ Dual MPPT 15600w	2	\$2,320.00	\$4,640.00
JC250	JC /250Ah C10 Tall Plate - Tubular Flooded battery / 2000cycle @50% DoD /12v.	48	\$289.00	\$13,872
CBL25C	25mm Copper Single Line (Black Red) for Battery wiring	144m	\$4.48	\$645
COS25	25mm/ open 8mm Cos type battery clamp.	124	\$0.36	\$45
BB255	DC CABLE COMBINER BUSBAR + External Box 10x08cm (Complete)	1	\$245.00	\$245
BT12- INVT	8 Battery rack & inverter back holder "table manner" (Steel) in white color (Optional)	6	\$210.00	\$0
BT12	8 Battery rack - "table manner" only (Steel) in white color (Optional)	6	\$96.00	\$0
ATS-1P	ATS- Dual Contactor + Timer + Relay (Complete) up to 80A max 3 phase	1 setup	\$362	\$362.00
DSP-1P	Indoor Control Display- Multiple in-out AMP & Volt Meter protection + C.Breakers	1 setup	\$100.00	\$100.00
	Wall Mount Electric Cabinet -90cm x 112cm	1	\$154.00	\$154.00
LBC4-6	6.0mm x 4 lines Power Cable on grid (White Color).	Per 1/m	\$6.80	\$0.00
ROS610	ROSEN 610w HafCell MonoC. PERC Photovoltaic Solar Panel Premium Class A	48 Panels	\$130.00	\$6,240
S-RACK	Customized Fortified,Rust Resistant Rack+ Complete Base& Setup+ all accessories.	48 Panels	\$55.00	\$2,640
S-RACK-INST	Outdoor Solar Rack assembly & Welding works including labour and other installation.	48 Panels	\$10.00	\$480
CB-VP	Panel DC-Circuit Breaker - Multi Surge Protective Panel Circuit Indoor Panel board	2 setup	\$128.00	\$256
TRSD25M	Liban Cable - TORSAGE Aluminium Panel2MPPT Black outdoor cable (16mm x 2)	Per 1/M	\$1.00	\$0
LBC-1-6	Liban Cable - Pure Copper Twin RedBlack outdoor cable (6mm x 2)	Per 1/M	\$3.40	\$0
ECH20	CANALI- Outdoor Panel Cable tube protection PVC-FLEX -Grey 20mm	Per 1/M	\$1.90	\$0
OUTBX1	(13x13x7) Outdoor Junction Box + Copper Twin wire screw connectors. (25mm)	2	\$8.00	\$16
ACCSS1	Outdoor/ Indoor accessories:(Roll Bolt Screw, Cable tie, Wire Fastner, Nail Plugs)	Complete	\$115.00	\$115
TRSP	General Handeling charges & Transportation.	1 setup	\$500.00	\$500.00
INST	Complete Installation (Indoor / Outdoor)	1 setup	\$2,400.00	\$2,400.00
WRTY201JC	ALL TECH INSURANCE (Battery Risk Cover)	36 MONTHS	INCLUDED	INCLUDED
WRTY201GR	ALL TECH INSURANCE (Inverter Risk Cover) & Free maintenance + Follow up vists	36MONTHS	INCLUDED	INCLUDED

TOTAL AMOUNT US \$32,710.00

Discount % USD

NET TOTAL AMOUNT \$32,710.00

Duration Battery Consumption time-frame @80% (28A x 3) constant load from fully charged down to 80% depth of discharge: 8.7hrs

NOTE Prices includes the ALL TECH INSURANCE (REF.CODE101)

Payment 80% upon agreement/ 20% upon delivery

Q,Validity Prices are subject to change without further notice

www.lse.com.lb